

## P.G. Thirolf, C. Weber, R. Meißner, P. Müller LMU München



P.G. Thirolf, LMU München




# MLLTRAP: Infrastructure



## General properties in exp. hall:

- 8 x 5 m<sup>2</sup> floor space (includes electronics, control desk)
- limited access around high-field magnet (rest: free access)
- max. weight on floor ca. 1000 kg/m<sup>2</sup>
- min. roof height 4.5 m
- position within crane range
- air conditioning/climatization: stable to  $\pm 1$  degree
- optical alignment capabilities (reference points/posts)



- no souces of magnetic stray fields in neighbourhood
- no sources of vibrations in neighbourhood





# Media supplies:

LMU

MLL

- electricity:
  - ca. 18x 230V (16A), 4x 400V (16A), 1x 400V (32A)
- cooling water (for standard turbo pumps):
  demineralized, ≤ 8 bar , ca. 0.3 m<sup>3</sup>/h
  standard water access in vicinity
- contribution to overall cooling power: < 10 kW
- compressed air: 5-7 bar
- liquid nitrogen: ca. 4000 l/year (100 l each ~10 days)
- liquid helium: ca. 800 l/year (200 l each ~90 days)
- nitrogen, helium gas bottles next to setup
- pump exhaust system
- helium recovery line system
- ethernet (ca. 4x), phone





- local data acquisition will be part of the experimental setup
- use of stable-ion source: (e.g. Kr,Cs, Rb)
- license for use of radioactive ( $\alpha$ , electron) calibration sources
- $\geq$  2 cabinets for small parts near setup
- (access to) detector preparation lab
- (access to) general storage area

(local control of e.g. Faraday cups/beam diagnostics would be convenient)







#### Ion injection conditions:

- tolerable distance to buncher ??

# Required, but not yet available:

- HV platform or pulsed drift tube ?
- local staff technician (routine operations, maintenance)

# MLLTRAP @ SPIRAL-2:

- German funding of personnel and equipment ??